

Truss Tech, Inc.

Manufacturer of Quality Engineered Floor & Roof Trusses

18541 Parkway Melfa, Virginia 23410
Phone: 757-787-3014 Fax: 757-787-1161

POLE BUILDING PACKAGES:

A typical package will include roof trusses with a 4/12 pitch @ 4'-0" o.c. 1'-0" top chord overhangs on all sides including gable ends. A panelized roof system to serve as purlins @ 2'-0" o.c. the purlins will be 2x4 syp. The roof panels are generally 8' x 8' and minimize the labor spent installing loose purlins one major advantage to this system is that the roof can be pre-assembled on the ground and gang lifted either in sections or the whole system depending on the size of the crane into place minimizing crane time in some cases to less than one hour. Keep in mind the roof will still require loose bracing for webs, gable ends & bottom chord, which we supply as loose material and can be installed after the roof is set.

We provide a panelized wall system which includes the outer supporting ring beam, 2x4 purlins @ 2'-0" o.c. and lateral bracing for the building. We also include truss headers to be installed over the large door openings. The panel sizes are dependent upon your pole spacing which is generally 6'-0" o.c. and the height of the building. The wall panels will be 2'-0" shorter than the height of the building to allow for a pressure treated purlin to be installed at grade which we do not provide. Any materials installed within 2'-0" of grade will need to be treated the only treated material we provide are the poles.

The poles will be 6x6 with a marine grade treatment approx. 6'-0" o.c. We include any non treated purlins that will be needed to supplement our panel system and any other necessary loose framing material including a 2x10 inner ring beam and 2x6 sub-fascia / rake boards. The package includes a specialized fastener for installing the panels which will substitute any thru-bolts or lag screws that a typical pole building would require and saves a considerable amount of time in labor, we also include any required mechanical fasteners such as hurricane ties.

The package includes a standard sized rollup door, residential overhead garage doors are not available from Truss Tech. We do not include any windows or personnel doors however our panels can be modified on site to accommodate those openings we do not make any allowance for the openings other than with regard to pole placement if we know in advance where they will be installed. Roofing and siding materials are a classic rib 29ga. painted metal with a 45yr. finish which includes ridge cap, foam closures, rake trim, outside corners, f/j channel, j channel, rodent guard and any other necessary accessories including fasteners. We do not include soffit or fascia trim in our package. If your would like to substitute vinyl siding we can remove the metal pricing and re-price with 7/16" osb sheathing to be sided over, again the lower 2' will need to be a treated plywood which we do not supply. We also include detailed CADD drawings and layouts including a placement diagram and provide any technical support needed to get through the project.

**-For more information please contact Tom or Ed
Tel: 757-787-3014 Fax: 757-787-1161 email: tom@trusstech.net**